

**BOQ - AC WORKS AT KELANAGAR BRANCH**

S. No.	DESCRIPTION	QUNTIY.	UNIT	RATE	AMOUNT
1	Suppy, Fixing, Testing & comissioning of following star rated <b>AC</b> units, with evaporator copper coil & imported refrigerant joints, with wireless remote controller ( <b>Make:- Bluestar / Voltas / LG</b> )				
(i)	Cassette 2 TON - INVERTER TECHNOLOGY	4.00	No.		
(ii)	Split 1.5 TON - INVERTER TECHNOLOGY	3.00	No.		
(iii)	Split 1 TON - INVERTER TECHNOLOGY	2.00	No.		
2	SITC of interconnecting <b>refrigerant pipe</b> work with closed cell elastomeric nitrile rubber tublar in sulation between each set of indoor & outdoor units as per specification, all piping inside the room shall be peoperly supported with MS hanger & clamps including cabling from indoor to outdoor unit.				
(i)	Refrigerant Pipe for 2 TONE AC - INVETER (Cassette)	95.00	Rmt		
(ii)	Split 2.0/1.5/1.0 TONE - INVERTER	55.00	Rmt		
3	Providing & fixing, testing and commissioning of wall mounted copper wound <b>voltage stabilizer</b> suitable for split all accessories. Input Voltage range : 140-280 V, Output : 230 V (Make:- LIVEGAURD/ Blue- Birds & Reputed Firm .)				
(i)	CAPACITY: 5 KVA	4.00	Nos		
(ii)	CAPACITY: 4 KVA	4.00	Nos		
4	SITC of rigid <b>CPVC piping</b> complete with fittings supports as per specification tions & duly insulated with 6mm thick closed cell nitrile rubber insulation.				
(i)	Drain Pipe for 2.0 Tone AC (Cassette)	70.00	Rmt		
(ii)	Drain Pipe for Split 2.0/1.5 TR (Split)	20.00	Rmt		
5	M.S. stand with monkey cage - [ In door & out door units ]	9.00	No		
6	Installation Charges .	9.00	No		
<b>Total in Rs</b>					
GST 18 %					
<b>Total including GST in Rs</b>					