

**BILL OF QUANTITY OF INTERIOR DESIGN AND FURNITURE WORKS FOR CANARA BANK, CPH BRANCH
AT PATNA**

Sl. No.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	Note-I: Anti-termite with Chloropyrphos of approved band and make to be done on all wooden surfaces.				
	Note-II: Wherever painting items are mentioned, these always include the base coats of primer required and a minimum of 2 coats of the Final paint. Anti-termite with Chloropyrphos of approved brand and make to be done on all wooden surfaces.				
1	Full ht. Partition Partly panelled and partly glazed & non Glazed :- Providing and fixing double skin partly panelled & partly glazed full height partition with frames of 50mm x38mm (finished size) GI frame work Steel section /Aluminium section /50mmx38mm (finished size) seasoned hardwood members (Gamhar,Malaysian salwood/ hollick) at maximum intervals of 450 mm x450mm with provision of bigger members at skirting, fixing to false ceiling (if provided) fixing to RCC Slab, beams ets, all wood work to be treated with 1st quality anti-termite pain and covered with 6mm thick BWP grade plywood at maximum intervals of 450mm x450 mm with Provision of bigger members at skirting, fixing to RCC slab, beams etc. And covered with 100 thick MDF board /6mm of BWP grade plywood respectively approved make on both side and 1mm thick (Greenlam/ Century) Laminate and pasted in the same as per typical design, on both sides so as to form a double skin partition to level 900mm and with 5.0mm clear float-glass make of glass she be Modi /Saint gobain,. all complete work with all materials, labour etc, as per drawing design specification and direction of Bank/ Architects (Materials:- Board MDF Prelaminated Board of century/Green/ Action tesa (Exterior)	S.Ft.	985.00		
2	Low ht. Partition:- Providing and Fixing low & Half height partitions 4' 6"with double skin panelling up to 3'-0" and 12mm thick clear float above frame less on the top and sides and sturdily fixed at the bottom on a polished teakwood all complete job with all other specifications and details to be as per item no.01 above and as per the design i.e. shown in sides of low ht. all complete work with all materials, labour etc, as per drawing design specification and direction of Bank/ Architects. Materials:- Board MDF Prelaminated Board of century/Green/ Action tesa (Exterior)	S.Ft.	1805.00		
3	(A) Providing and fixing work station table top 25mm with drawers Making and providing Desk-top with provision of wore manager having two sides vdertical support panels and modesty panel. All made of 18 mm thick Exterior grade MDF (Both side laminate) board. All Taedges shall be covered with teak wood lipings and front-edge shall be covered with 4mm PVC sheet selected colour /half round molding . All wooden surface shall be well polished with melamine polish.Keyboard unit as per design and specification to be included in the rate.				
	(B) Making and providing Desk-top with provision of wore manager having two sides vdertical support panels and modesty panel. All made of 18 mm thick Exterior grade MDF (Both side laminate) board side edges of drawers and cupboard shall molded in round shape with Gamhar wood. All drawers shall have Z shape powder coated MS runners with PVC sound less rollers. All wooden surface shall be polished with melamine/spirit polish all complete work as per drawing design specification and direction of Engineer-in –charge/Bank.				

	(C) Providing and fixing key board tray (as per design and specification at 1baove) try and made of PVC soundless rollers.				
	(i) L-shaped 1800mm x900mm x750mm for officers drawers (refer drawings) with 900mm x 400mm x750mm side rack attached with table (including CPU stand and footrest).	NO.	1		
	(ii) Table 1200mm x600mm x750mm for officers drawers (refer drawings) including CPU stand and footrest.	NO.	96		
	Materials:- Board MDF Prelaminated Board of century/Green/ Action tesa (Exterior), Hinge- Godrej make, sliding channel- Godrej make heavy duty, Lock- Godrej make in Drawer, The reat shall be inclusive all materials, labour and transportation etc, as per drawing design specification and direction of Bank.				
4	Making and fixing law high type storage cabinet with drawer and cupboard with shelf as per the drawing design all made of 18mm thick exterior grade MDF (both side laminate)board edges shall have Gamhar wood molding, drawer shall be run of "Z" type drawer slides with PVC rollers and all wooden surface shall be melamine polish all complete work with necessary and required hardware of standard quality all complete work the rate shall be inclusive of all materials labour and transportation etc. As per drawing design specification and direction of Bank (Materials :- Board MDF Prelaminated Board of Green (Exterior), Hinge- Godrej Make, Sliding channel- Godrej Make Heavy Duty century/Green/ Action tesa	S.Ft.	305		
5	Providing and fixing Wall panelling with seasoned Malaysian salwood members of the minimum size 50mm x25mm (a bigger size may be required at the corners, etc) firly affixed to the supporting wall at a maximum spacing of 450mm x450mm c/c (the spacing shall need to be closer, if the room grid so dictates), 5.5 mm thick Exterior grade MDF (Both side laminate)board firmly fixed to the wooden frame and covered with polish. The wooden frame shall be coated with ant termite paint (Choloropgyrophos) teakwood molding 50mmx 50mm at top and bottom of column all complete work the rate shall be inclusive of all materials, labour and transportation etc. As per drawing design specification and direction of Engineer-in charge. (Material:- Board MDF century/ green// Action tesa make	S.Ft.	650		
6	(HYDRAULIC DOOR CLOSER) Providing and fixing Hydraulic door closers of specified brand, all complete as per instructions of Architect / Employer.	Each	5.00		
7	(LOCKS) Providing and fixing "Godrej Night Latch" / "Godrej Mortice Lock" in required places, all complete with fixing, fitting, etc.	Each	3.00		
8	3 Seater Sofa - Size 3 Seater (2130x870x870)mm & Seat Height 400mm. Frame used is treated American pine wood with termite free & borer free. Soft & comfortable cushion with high density and resilient foam. Frame used is Treated american pine wood & the wood used in sofa has been 8% moisture, this prevents the wood from wrapping and bending. all wood used is termite free and borer free. Foam of sofa comfortable cushion with high density and resilient foam. all apholstry materials used in specially designed. all plywood used in M R Garde and are made by DURIAN &GODREJ	Each	2.00		
9	FALSE CEILING				
i)	Gypsum board false ceiling with Vertical band /drop of 6" Gypsum board false ceiling with Vertical band /drop of per detail drawing & instructions of Architect				

	<p>Providing and fixing in position Gypsum Board False Ceiling including Two coats of Plastic emulsion Paint of appd.quality as per manufacturer's specifications and instructions with 12.5 mm thick 'Gypboard' Screw-fixed to the underside Of suspended G.I. grid. G.I. grid should be Constructed and suspended from the main ceiling as per manufacturer's instructions and as per specifications using Original Co. Specified Framework Sections G.I.24 gauge The Gypboard should be fixed to G.I. grid with 25 mm long Drawali Screws. The 'Gypboard ' to be used should be 12.5mm thick tapered edge boards. The boards should Be taped and filled from underside to give smooth, seamless ceiling. The rate should include necessary additional ceiling sections and intermediate channels openings for light fixtures, A.C. ducts, vertical drops, offsets. etc.</p>				
	<p>Additional Intermediate channels should be fixed to strap hangers for additional support to prevent strap hangers from buckling/swaying at every 1200 mm. Item to be completed in all respect including necessary sleeves for ducts finishing of joints cut outs supports for A.C. grills, light fixtures, speakers etc.Make: Gypsum board-India Gypsum. Panint-Asian/ ICI The rate should include necessary additional ceiling sections and intermediate channels openings for light fixtures, A.C. ducts, vertical drops, offsets.and with two coats of putty, two coats of approved primer, and three coats of approved lustre pain (make:-USG Boral/Saint gobain/Hicem)</p>	SQ.FT.	2500.00		
ii)	Grid False Ceiling				
	<p>Providing & fixing false ceiling at all heights with GRG (Glass Fibre Reinforced Gypsum) false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having moisture content less than 2%, humidity resistance of 99%, NRC 0.50 to 0.75 as per IS 8225:1987, Non combustible as per BS 476 (part-4)-1970 and light reflectance of 85% (minimum) to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 15x32 mm of length 3000 mm, cross - T of size 15x32 mm of length 1200 mm and secondary intermediate cross-T of size 15x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x2 mm. Galvanised iron perimeter wall angle of size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40 mm long dry wall SS screws. The work shall be carried out as per specifications, drawing and as per directions of Engineer-in-Charge (make:-USG Boral/Saint gobain/Hicem)</p>	SQ.FT.	1695.00		

10	Main Entrance Door: Full.ht.Glass Partitions (WITH DOOR)Entrance side Providing and fixing 12 mm thk. full ht. Toughened Glass partitions with etched horizontal liner of 1"ht. and 1/2"clear space in between as per design ,Rate should be inclusive of additional Alluminium profile fixed in the flooring and above finished false ceiling level with necessary patch fittings as required to hold the glass partition. All exposed edges surfaces should be machine polished edges. The Rate shall be also inclusive of floor spring ,necessary hardware 3'-0"ht. Matt steel door handles with floor locking arrangement of Enox co. etc. Complete as per desigens and details from the Architects.The rate shall be Inclusive of Horizontal Etched Lining in between 3' to 6' ht. horizontal etched lining of 1"frost and 1/2" clear as per design etc. complete. Supplying and fixing banks logo – sticker as per drawing and design. Glass wall as per design and instruction by Architect /Enginee	S.Ft.	145.00		
11	vertical blinds : Providing & fixing levelor 10mm vertical blinds having top rail 39mmX34mm hjgh with wall thicknessof 1.2mm having 25mm decorative insert. Control unit shall be of Derlin. Plastic runner shall be moulded from Derlin plastic with artification head rail & the top end of the louver fabric shall be polyster viscose/polyster yarn dyed in fast colour with or without protective coating on louvers with chemical for stain resistance and soil repetancy and shall have GI weight and steel/polymer ball chain for spacing. The top rail should be fixed on bracket of 14 SWG galvanized spring steel fixed firmly on walls by nylon plug and screw as per approved design and direction of the Architect. (make:-Vista, Universal)	SQ.FT.	432.00		
	TOTAL				
	G.S.T(Extra as applicable)				
	Notes:-				
	Contractor to Note that:-				
a)	Footrests to be provided (laminated) with each table / counter without any extra charges, @ 1 per person.				
b)	Extra members, wherever required for stability / otherwise, to be provided with the required finish without ant extra charges.				